



E019-1.5 ELECTRIFIED INTERMEDIATE PIVOT, 1 ½" OFFSET, HANDED








TOP VIEW
RIGHT HANDED PIVOT
SHOWN





NOTES:

- 1. PIVOTS DRILLED FOR $1/4-20 \times 3/4$ FHMS OR #14 x 2" FHWS.
- 2. REINFORCING BY OTHERS.
- 3. IT IS THE DOOR AND FRAME MANUFACTURERS RESPONSIBILITY TO CHECK THE HARDWARE SCHEDULE AND PREP THE DOORS AND FRAMES.
- 4. MAXIMUM DEGREE OF OPENING, 180°, TRIM PREMITTING.

DOOR AND FRAME PREPARATION

- PREPARE DOOR & FRAME PER DRAWING ABOVE.
- THROUGH WIRE TYPE PIVOTS ARE NON-LOAD BEARING AND MUST BE MOUNTED IN THE CENTER PIVOT POSITION ONLY.
- DO NOT ATTEMPT TO DISASSEMBLE THE PIVOT, IT MUST BE INSTALLED ASSEMBLED. IF PIVOT IS DISASSEMBLED, MANUFACTURER'S WARRANTY WILL BE VOID.
- WIRE CLEARANCE HOLES MUST BE FREE OF BURRS AND SHARP EDGES.
 CHECK TO MAKE SURE THAT PIVOT FITS FREELY IN PREP TO AVOID DAMAGE AND/OR SHORTENED LIFE.
- **●** DO NOT FORCE PIVOT INTO PREP HOLES.

INSTALLATION

- 1. HANG THE DOOR ON THE TOP AND BOTTOM PIVOTS FIRST. (NOTE: THESE ARE NON-ELECTRICAL PIVOTS).
- 2. ATTACH WIRES IN ACCORDANCE WITH PROJECT WIRING DIAGRAMS.
- 3 OPEN DOOR TO 90° OR MORE FOR ACCESS TO JAMB PREPS
- 4. EXTRACT INTERIOR WIRING THROUGH THE PREP HOLES FROM THE DOOR AND JAMB.
- 5. TERMINATE WIRE CONNECTIONS WITH APPROPRIATE CRIMP SPLICES OR WIRE NUTS.

 NOTE: IT IS HELPFUL TO STAGGER TERMINATIONS. THIS ALLOWS FOR EASY INSERTION OF WIRES THROUGH PREP HOLES.
- 6. DO NOT HANG PIVOT BY WIRES DURING INSTALLATION OR SERIOUS DAMAGE COULD OCCUR.
- 7. INSULATE ALL ENDS OF UNUSED WIRES.
- 8. AFTER ALL TERMINATIONS ARE COMPLETED, CAREFULLY SLIDE WIRES THROUGH PREP HOLE MAKING SURE THAT WIRES ARE PLACED SO THEY WILL NOT BE CUT OR PINCHED AS PIVOT IS INSTALLED.



www.abhmfg.com E-mail: abhinfo@abhmfg.com Architectural Builders Hardware Mfg., Inc. 1222 Ardmore Ave., Itasca, IL 60143

1222 Ardmore Ave., Itasca, IL 60143 © 2018 ABH Mfg., Inc. 630.875.9900; FAX 800.9FAXABH (932.9224) printed in USA

E019-1.5-07.DWG

E019-1.5

PAGE 1 OF 1

REVISED 10-17-18